ClearTester CT-300


Elear**Test**

Quick Start

IMPORTANT SAFETY INFORMATION

Read and understand these instructions prior to use. These operating instructions are not a substitute for proper

training in the use of this equipment. Refer to the Instruction Manual for additional information.



TEST TRANSFORMERS

Verify both primary and secondary sides are deenergized.

Connect the ClearTest as shown for 1Ø transformers and press and hold the TEST button.


The ClearTest performs a brief self test indicated by the lights and the beeper and then tests the transformer.


Results are displayed as OK, SHORT or OPEN.



across the secondaries OK

across the primary






For 3Ø

transformers, the ClearTest leads are connected from neutral and across each pair of phases. When all connections are proper and the transformer itself is good, the ClearTest will beep and show OK.

The OPEN indication designates a bad connection or an open transformer winding. A SHORT indication designates a short from phase to neutral or phase to phase in the transformer or the connections to it.


For Y (wye) connections, test the primary and secondary sides of the transformer as follows:

- X1-X2 Transformer OK
 X2-X3 Transformer OK
 X1-X3 Transformer OK
 H1-H2 Transformer OK
 H2-H3 Transformer OK
 H1-H3 Transformer OK
- H1-H0 Transformer OK
- H2-H0 Transformer OK
- H3-H0 Transformer OK




Primary

Secondary



Y Connection



Delta Connection

For Δ (delta) connections, test the primary and secondary sides the same as the Y except omit the connections to X0 and H0.

- H1-X1 **T**ransformer OK if both H0
- H2-X2 hand X0 are grounded,
- H3-X3 **J** otherwise OPEN
- H0-X0 SHORT, if both sides are grounded, otherwise OPEN

Replace both ClearTest batteries if it does not pass the self test as indicated by a short beep.

For the complete instructions, refer to the Instruction Manual.

